HUTTY

RESIDENTIAL DIGITAL QUANTITY SURVEYING PLATFORM

CONSTRUCTION ESTIMATE & BOQ DOSSIER

Duplex
1,440 sq.ft Built-Up Area

Authoritative pre-construction digital QS dossier for Bangalore.
Includes Works BOQ (Section A), Materials Needed (Section B), Services & Fixtures Schedule (Section C), and Cost Summary & Payment Plan (Section D).

DIRECT CONSTRUCTION BUDGET	DIRECT RATE	EST. TIMELINE
₹38,35,855	₹2,664 / sq.ft	9 Months
Core Direct Execution (Zero Margin/GST)	PREMIUM specification tier	2 floor(s) · Duplex

SECTION B · MATERIALS	SECTION C · FIXTURES & SERVICES	EXECUTION LABOUR
₹22,57,097	₹7,55,590	8,23,168
What We Consume	What We Install	Civil & Finishing Trades

PROJECT REFERENCE **HT-2026-VERIFY-01**	PREPARED FOR **Founder Inspection**
DATE ISSUED **01 Nov 2026**	EXECUTION MODE **Independent Self-Build**
PLOT DIMENSIONS **40 × 30 ft**	RATE MASTER DATASET **HUTTY-RM-2026.1**
DATA SOURCE **2026-Q1 Baseline**	CALCULATION ENGINE **v2.6.0**

IMPORTANT ESTIMATE NOTE
This is an early estimate to help you plan. Final costs and quantities may change after the site, drawings and material choices are checked.

1. PROJECT PARAMETERS & BUILT-UP AREA

PLOT AREA	BUILT-UP AREA	BASE CONST. COST	EST. TIMELINE
1,200 sq.ft	**1,440 sq.ft**	**38,35,855**	**9 months**
40×30 ft	2 floor(s)	3,860/sq.ft	Duplex

2. KEY STRUCTURAL & CONCRETE QUANTITIES (DERIVED)

STRUCTURAL STEEL	PORTLAND CEMENT	TOTAL RCC CONCRETE	BLOCK WALL AREA
4.32 Tonnes	**576 Bags**	**68.91 m³**	**5,270.5 sq.ft**
4,320 kg	50 kg / bag	Footing + Col + Slab	3,485 Nos

FOOTING CONCRETE	COLUMN CONCRETE	SLAB CONCRETE	BLOCK CONSUMPTION
16.48 m³	**13.48 m³**	**38.95 m³**	**5,270.5 sq.ft**
Pads & Footings	Structural Columns	Slabs & Beams	AAC Blocks coverage

SECTION A — WHAT WE BUILD · COMPREHENSIVE WORKS BOQ

SL	TRADE ACTIVITY & DESCRIPTION	QTY / UNIT	RATE (₹)	AMOUNT
1	Topsoil Clearing & Benchmark Boundary Demarcation · Total Station Survey incl. grid layout	1,200 sq.ft	₹12	**₹14,400**
2	Excavation – Column Footing Pits & Sump Trench (JCB) · Mechanical Excavation 180 kN/sqm SBC assumption	33.71 m³	₹190	**₹6,405**
3	Anti-Termite Pre-Construction Soil Chemical Treatment · Chlorpyrifos 20% EC IS 6313 compliant chemical emulsion	1,200 sq.ft	₹18	**₹21,600**
4	Temporary Site Shed, Storage Godown & Electrical Setup · GI Sheet Enclosure incl. 3-phase connection	1 Units	₹75,000	**₹75,000**
5	PCC M10 Levelling Bed below Column Footings · UltraTech 100mm thickness (1:3:6)	5.99 m³	₹3,200	**₹19,168**
6	Isolated / Combined Column Footing RCC M25 · UltraTech / ACC RMC 50mm clear cover to rebar	16.48 m³	₹4,800	**₹79,104**
7	Footing Reinforcement TMT Fe 550D Bar Bending · Tata Tiscon IS 13920 seismic foundation cage	0.86 Tonnes	₹78,000	**₹67,080**
8	Plinth Tie Beam RCC M25 Casting · UltraTech / ACC RMC Continuous ring plinth beam	5.99 m³	₹4,800	**₹28,752**
9	Plinth Tie Beam TMT Reinforcement Fe 550D · Tata Tiscon continuous tie beam rebar	0.35 Tonnes	₹78,000	**₹27,300**
10	Granular Earth Backfilling & Plate Compaction · Quarry Dust + Red Earth 150mm watered compacted layers	10.2 m³	₹200	**₹2,040**
11	Damp Proof Course (DPC) M20 with Waterproofing · Dr. Fixit Pidiproof LW+ 50mm thick waterproof DPC layer	720 sq.ft	₹18	**₹12,960**
12	RCC Columns M25 Casting (Ground to Top Floor) · UltraTech / ACC RMC pump placed with needle vibrator	13.48 m³	₹4,800	**₹64,704**
13	RCC Beams & Roof/Floor Slabs M25 Monolithic Pour · UltraTech / ACC RMC 125-150mm slab + 200×450mm beams	38.95 m³	₹4,800	**₹1,86,960**
14	RCC Staircase Waist Slab & Folded Steps · UltraTech / ACC RMC 150mm waist slab with risers	4.49 m³	₹4,800	**₹21,552**
15	Column TMT Reinforcement Fe 550D Caging · Tata Tiscon main vertical bars + ties @100mm	1.3 Tonnes	₹78,000	**₹1,01,400**
16	Floor Slab & Beam TMT Reinforcement Fe 550D · Tata Tiscon top/bottom mesh + cranked bars	1.81 Tonnes	₹78,000	**₹1,41,180**
17	Scaffolding & Film-Faced Plywood Formwork System · Cuplock Staging System waterproof shuttering ply with oiling	1,296 sq.ft	₹55	**₹71,280**
18	AAC Block 150mm External Perimeter Masonry Wall · Birla Aerocon AAC Blocks thin-bed polymer adhesive joint	32.85 m³	₹3,800	**₹1,24,830**
19	AAC Block 100mm Internal Partition Masonry Wall · Birla Aerocon AAC Blocks 3mm joint mortar bed	26.88 m³	₹3,230	**₹86,822**
20	RCC Lintel Beams with 2-legged Stirrups over Openings · M20 in-situ concrete 200mm × 150mm lintel band	43 Metres	₹850	**₹36,550**
21	Precast RCC Chajjas / Sunshades over Windows · M20 RCC + drip groove 450mm projection with slope	18 Metres	₹1,200	**₹21,600**
22	GI Chicken Mesh 22g at RCC-Masonry Wall Junctions · GI 22g 150mm width prevents hairline shrinkage cracks	576 Metres	₹18	**₹10,368**

SL	TRADE ACTIVITY & DESCRIPTION	QTY / UNIT	RATE ()	AMOUNT
23	Internal Cement Plaster 12mm (Smooth Trowel Finish) · OPC 53 + P-Sand (1:4) smooth sponge / steel trowel finish	4,093 sq.ft	28	**1,14,604**
24	External Sand-Faced Cement Plaster 20mm (Double Coat) · OPC 53 + M-Sand (1:5) rough cast base + sponge finish	2,318 sq.ft	36	**83,448**
25	Terrace Brick Bat Coba & Integral Waterproofing Treatment · Dr. Fixit + IWC IS 3067 slope with round vatas	720 sq.ft	85	**61,200**
26	Roof Cement Screed & 2% Water Drainage Slope · OPC 53 screed mortar guarantees zero water ponding	720 sq.ft	45	**32,400**
27	Parapet Wall RCC / Masonry 900mm Height with Plaster · M20 RCC + Plaster 900mm fall protection barrier	112 Metres	2,200	**2,46,400**
28	Living Room Flooring Finish (Material & Laying) · Granite Slab MYK adhesive + epoxy grout	344 sq.ft	220	**75,680**
29	Bedrooms Flooring Finish (Material & Laying) · Wooden Laminate laid over 40mm mortar screed	440 sq.ft	180	**79,200**
30	Kitchen & Dining Flooring Finish (Material & Laying) · Matte Anti-Skid Vitrified stain-resistant non-porous tile	247 sq.ft	135	**33,345**
31	Bathroom Anti-Skid Floor Tiles (Material & Laying) · Matte Finish Vitrified R10/R11 slip-resistant finish	137 sq.ft	115	**15,755**
32	Parking & Utility Heavy-Duty Flooring · Flamed Granite heavy axle load rated	137 sq.ft	160	**21,920**
33	Balconies Exterior Weatherproof Flooring · Wooden Finish Tiles UV and weather-resistant tile	69 sq.ft	125	**8,625**
34	Bathroom Wall Tiles (Dado Cladding up to selected height) · Kajaria Glamour Wall Full Height (Ceiling)	746 sq.ft	95	**70,870**
35	Kitchen Backsplash Wall Dado Tiles · Kajaria Satin Glazed 4 ft	48 sq.ft	95	**4,560**
36	Granite Slabs for Staircase Steps, Risers & Landings · Sadahalli / Jet Black Granite 20mm 3 anti-skid grooves + full bullnose	180 sq.ft	320	**57,600**
37	Tile Polymer Adhesive & Stain-Free Epoxy Grouting · MYK Laticrete 254 100% bed coverage with zero voids	1,374 sq.ft	22	**30,228**
38	Main Entrance Grand Door (Frame + Shutter + Hardware + Lock) · Premium Teak 4.0 ft × 7.0 ft	1 Sets	65,000	**65,000**
39	Internal Bedroom & Living Space Door Set (Hardwood Frame + Shutter + Mortise) · Flush Door 3.0 ft × 7.0 ft	7 Sets	12,500	**87,500**
40	Waterproof Bathroom Door Set (WPC/FRP Frame + Water-Resistant Shutter) · FRP / WPC Laminated 2.5 ft × 7.0 ft	4 Sets	13,500	**54,000**
41	Solid Teak Wood Main & Hardwood Internal Door Frames · Plantation Teak 4×3 inch seasoned kiln-dried hardwood	52 Metres	1,800	**93,600**
42	SS Mortise Lock Sets, Handles, Hinges & Tower Bolts · Godrej / Yale SS 304 6-lever mortise lock + SS hinges	7 Sets	3,200	**22,400**
43	Bedroom 2-Track Glazed Window with Mosquito Mesh (3 Nos) · uPVC – Standard uPVC 3 Nos • 5.0 ft × 4.0 ft (Total 60 sq.ft)	60 sq.ft	550	**33,000**
44	Living Room 3-Track Picture Window (Full Height) (2 Nos) · uPVC – Standard uPVC 2 Nos • 6.0 ft × 5.0 ft (Total 60 sq.ft)	60 sq.ft	550	**33,000**
45	Kitchen Sliding Window with Exhaust Louver Provision (1 Nos) · uPVC – Standard uPVC 1 Nos • 4.0 ft × 3.0 ft (Total 12 sq.ft)	12 sq.ft	550	**6,600**
46	Bathroom Louvered Ventilator with Exhaust Opening (4 Nos) · uPVC – Standard uPVC 4 Nos • 2.0 ft × 3.0 ft (Total 24 sq.ft)	24 sq.ft	550	**13,200**
47	Dining Room Glazed Sliding Window (1 Nos) · uPVC – Standard uPVC 1 Nos • 5.0 ft × 3.0 ft (Total 15 sq.ft)	15 sq.ft	550	**8,250**
48	Utility Service Ventilator Window (1 Nos) · uPVC – Standard uPVC 1 Nos • 4.0 ft × 2.0 ft (Total 8 sq.ft)	8 sq.ft	550	**4,400**
49	MS Safety Grille Fabrication, Primer & Polyurethane Fitting · SS 304 / MS Grille powder coated black safety grill	134 sq.ft	280	**37,520**
50	1.5 sq.mm FRLS Copper Wire Pulling (Lighting & Fan Circuits) · Mid-range (V-Guard) 1.5 sq.mm Phase, Neutral & Earth loop conductors	400 Metres	28	**11,200**
51	2.5 sq.mm FRLS Copper Wire Pulling (Power Sockets & TV/Data Outlets) · Mid-range (V-Guard) 2.5 sq.mm modular socket & console power circuits	550 Metres	44	**24,200**
52	4.0 sq.mm FRLS Copper Dedicated Circuit Wire (AC & Geyser Loads) · Mid-range (V-Guard) 4.0 sq.mm dedicated home-run appliance circuits	176 Metres	68	**11,968**

SL	TRADE ACTIVITY & DESCRIPTION	QTY / UNIT	RATE ()	AMOUNT
53	6.0 sq.mm FRLS Copper Sub-Main Distribution Risers & EV Supply · Mid-range (V-Guard) 6.0 sq.mm Main DB to Floor Sub-DBs + EV Charger line	35 Metres	102	**3,570**
54	Heavy-Duty PVC Conduit Pipe & Junction Boxes Embedded in Walls · Precision PVC ISI 25mm fire-retardant conduit	272 Metres	35	**9,520**
55	Modular Switches, Power Sockets & Regulator Plates · Mid-range (V-Guard) child-safe shuttered sockets	74 Modules	185	**13,690**
56	LED Concealed Spotlights & Batten Points Fitting · Philips / Havells LED warm/neutral white CRI>85	40 Points	1,200	**48,000**
57	Chemical Earthing Pits with Copper Electrode (x2 Pits) · Marconite Gel Earth System < 1 Ohm verified resistance	2 Units	22,000	**44,000**
58	Distribution Boards with MCB, RCCB & Isolators · Schneider / Legrand DB 30mA human shock protection	2 Units	24,000	**48,000**
59	Armoured Main Feeder Cable from Supply Meter to Panel · 4 Core 16 sq.mm XLPE underground GI trench run	15 Metres	1,800	**27,000**
60	CPVC SDR 11 Hot & Cold Water Concealed Pipe Lines · Ashirwad 10 bar SDR 11 at 82°C (IS 15778)	117 Metres	140	**16,380**
61	SWR Soil, Waste & Rainwater Drainage Pipe Lines · Supreme Ring-fit SWR 110mm + 75mm dia lines	66 Metres	340	**22,440**
62	Stainless Steel Floor Traps & Cockroach-Proof Gratings · Jaquar / Cera SS Floor Trap 50mm water seal depth	8 Units	850	**6,800**
63	Sanitaryware & CP Brass Bathroom Fixture Sets · Premium (Jaquar / Kohler / Grohe) WC + basin + diverter + shower	4 Sets	38,000	**1,52,000**
64	Overhead 4-Layer Anti-Bacterial Water Tank (1500L) · Sintex 4-layer UV with auto ball-valve & overflow line	1 Units	28,000	**28,000**
65	Constant Pressure Booster Pump & Sump Delivery System · Grundfos CM / Wilo 0.75HP VFD constant pressure pump	1 Units	35,000	**35,000**
66	Kitchen Double-Bowl SS 304 Sink with Swivel Mixer · Nirali / Franke 304 304 grade anti-scratch with mixer tap	1 Units	14,500	**14,500**
67	Interior Gypsum / Acrylic Wall Putty + Alkali Resistant Primer · Acrylic Putty + Primer 2 coats putty + 1 coat primer	4,093 sq.ft	16	**65,488**
68	Interior Premium Emulsion Acrylic Emulsion (2 Coats) · Asian Paints sheen washable interior coating	4,093 sq.ft	29	**1,18,697**
69	Exterior Ultima Weather Proof Emulsion Coating (2 Coats) · Asian Paints UV resistant anti-algal exterior paint	2,318 sq.ft	34	**78,812**
70	Bathroom Sunken Slab & Wall Upturn Elastomeric Waterproofing · Dr. Fixit Fastflex 2C 1.0 ft vertical wall upturn membrane	194 sq.ft	120	**23,280**
71	Energy-Efficient BLDC 28W Ceiling Fans with Remote · Atomberg Renesa BLDC 28W brushless DC motor, 5-speed	4 Units	6,500	**26,000**
72	Modular Kitchen Cabinets, Marine Ply Carcass & Counter · Sleek / Haecker Modular Quartz countertop + BWP carcass	12 Metres	18,000	**2,16,000**
73	Staircase Railing (SS 304 with Toughened Glass) · SS 304 / MS Fabricated AISI SS 304 grade balusters with 10mm toughened glass panels and 50mm dia handrail	24 Metres	1,850	**44,400**
74	Balcony Safety Railing (SS 304 with Toughened Glass) · SS 304 / MS Grille Weather-resistant SS 304 side spigots with 10mm clear toughened glass for balconies	24 Metres	1,650	**39,600**
75	Terrace Slab Safety Parapet Railing (3.0 ft height) · Tubular MS Railing 3-tier horizontal MS tubular safety rail anchored on terrace slab perimeter	45 Metres	450	**20,250**
76	Main Driveway Compound Gate (MS Designer Sliding / Swing Gate (10x6 ft)) · MS Fabricated Gate Architectural heavy gauge MS frame with sheet accents, roller track, hinges and lock	60 sq.ft	420	**25,200**
77	Overhead Water Tank Access Cat Ladder with Safety Rungs · GI / MS Cat Ladder 15 ft vertical hot-dip galvanized or MS safety caged rung ladder anchored to RCC wall	1 Units	9,500	**9,500**
78	Balcony French Sliding Door Set (2.5-Track Aluminium / UPVC) · Fenesta / Geeta Aluminium 5.0 ft × 7.0 ft 2.5-track sliding door with 6mm toughened glass and SS mosquito mesh	2 Sets	18,500	**37,000**
SECTION A TOTAL — WHAT WE BUILD (WORKS BOQ)				**38,35,855**

1. CORE MATERIALS NEEDED SUMMARY

STRUCTURAL STEEL	PORTLAND CEMENT	SAND & AGGREGATES	BLOCK WALL COVERAGE
4.32 Tonnes	**576 Bags**	**3,672 CFT**	**5,270.5 sq.ft**
4,320 kg	50 kg / bag	M-Sand + P-Sand + Metal	3,485 Nos

SECTION B — WHAT WE CONSUME · ITEMIZED MATERIALS NEEDED

SL	MATERIAL & BRAND SPECIFICATION	QUANTITY	UNIT RATE	TOTAL
1	TMT Reinforcement Steel (Fe 550D / Fe 500D) Tata Tiscon · IS 1786 certified, high ductility corrosion-resistant thermo-mechanically treated rebar	4.32 Tonnes	₹78,000	**₹3,36,960**
2	Portland Cement (OPC 53 Grade / PPC) UltraTech · IS 269 / IS 1489 certified 50 kg moisture-proof sealed bags	576 Bags	₹420	**₹2,41,920**
3	Manufactured Concrete Sand (M-Sand Zone II) Licensed Quarry Standard · Zone II double-washed cubical shape manufactured sand, silt content < 3%	864 CFT	₹65	**₹56,160**
4	Fine Plaster Sand (P-Sand) Licensed Quarry Standard · Zone IV ultra-fine washed plastering sand for smooth internal & external wall finish	864 CFT	₹70	**₹60,480**
5	Coarse Metal Blue Granite Aggregate (20mm & 12mm) Crushed Granite Standard · IS 383 angular crushed blue metal granite aggregate (60:40 20mm/12mm blend)	1,944 CFT	₹52	**₹1,01,088**
6	Autoclaved Aerated Concrete (AAC) Blocks Birla Aerocon AAC Blocks · IS 2185 Part 3, 600 × 200 × 150 mm, oven-dry density 600 kg/m3 (5% wastage)	3,485 Nos.	₹85	**₹2,96,225**
7	Vitrified Floor Tiles & Living Surface Cladding Granite Slab · Double-charged vitrified tiles / granite slabs with 7% cutting buffer	1,374 sq.ft	₹220	**₹3,02,280**
8	Ceramic Wall Dado & Kitchen Splashback Tiles Kajaria / Somany Satin Wall · 600×300mm digital glazed wall tiles for bathroom wet walls and kitchen counter	794 sq.ft	₹85	**₹67,490**
9	Interior Wall & Ceiling Emulsion Paint Premium Emulsion · Premium Emulsion (2 coats over putty primer)	91 Litres	₹380	**₹34,580**
10	Exterior Anti-Fungal Weatherproof Emulsion Premium Emulsion Apex Ultima · Silicone acrylic elastomeric exterior weather coating (7-year warranty)	39 Litres	₹420	**₹16,380**
11	White Polymer Modified Acrylic Wall Putty Birla White / JK WallMaxx · Water-resistant white cement based smooth surface leveling coat	2,251 kg	₹32	**₹72,032**
12	2-Component Polymer Elastomeric Waterproofing Membrane Dr. Fixit Fastflex 2C / SikaTop Seal 107 · Flexible cementitious waterproof coating for sunken slabs, terrace, and sump	1,217 sq.ft	₹65	**₹79,105**
13	CPVC SDR 11 Hot & Cold Water Pipes Ashirwad · SDR 11 chlorinated polyvinyl chloride pipes rated for 82°C at 10 bar (IS 15778)	117 Metres	₹140	**₹16,380**
14	SWR Ring-Fit Drainage & Soil Pipes (110mm & 75mm) Supreme / Prince SWR · Type B rubber ring seal leak-proof soil, waste, and rainwater drainage pipe	66 Metres	₹180	**₹11,880**
15	1.5 sq.mm FRLS Copper Electrical Wire (Lighting & Fans) Mid-range (V-Guard) · Flame Retardant Low Smoke IS 694 copper single-core wire	400 Metres	₹28	**₹11,200**
16	2.5 sq.mm FRLS Copper Electrical Wire (Sockets & Consoles) Mid-range (V-Guard) · Flame Retardant Low Smoke IS 694 copper single-core wire	550 Metres	₹44	**₹24,200**
17	4.0 sq.mm FRLS Copper Dedicated Circuit Wire (AC & Geysers) Mid-range (V-Guard) · Flame Retardant Low Smoke IS 694 heavy appliance conductor	176 Metres	₹68	**₹11,968**
18	6.0 sq.mm FRLS Copper Sub-Main Distribution Risers & EV Supply Mid-range (V-Guard) · Flame Retardant Low Smoke IS 694 sub-main distribution cable	35 Metres	₹102	**₹3,570**
19	Heavy-Duty PVC Conduit Pipe (25mm ISI Embedded) Precision PVC ISI · 25mm diameter heavy-gauge rigid PVC conduit with accessories	272 Metres	₹35	**₹9,520**
SECTION B TOTAL — PHYSICAL MATERIALS				**₹17,53,418**

MATERIAL CONSUMPTION & RATE INVARIANCE NOTICE

Material quantities are determined directly by your house size and layout. Changing brand selections (e.g. Tata Tiscon vs JSW Steel, or UltraTech vs ACC Cement) modifies the unit rate and cost total while keeping the physical quantities consistent (tonnes, bags, CFT, sq.ft, litres).

1. SERVICES & INSTALLED SYSTEMS OVERVIEW

ELECTRICAL POINTS	PLUMBING OUTLETS	SANITARY SUITES	DOORS & WINDOWS
99 Points	**30 Points**	**4 Suites**	**24 Units**
40 lights · 39 sockets	18 supply · 12 drain	4 EWCs · 4 basins	12 doors · 12 windows

SECTION C — WHAT WE INSTALL · SERVICES & FIXTURES SCHEDULE

1. ELECTRICAL SERVICES & EQUIPMENT — Subtotal: 67,690

SL	ITEM / SPECIFICATION	QTY / UNIT	RATE ()	AMOUNT
15	Modular Switch, Socket & Regulator Plates Mid-range (V-Guard) · Polycarbonate flame-retardant plates with child-safe shutters (All Rooms & Common Areas)	74 Modules	185	**13,690**
16	Concealed LED Spotlights & Batten Fittings Philips / Havells · 12W / 18W CRI>85 warm/neutral white recessed fixtures (All Ceilings & Corridors)	40 Points	450	**18,000**
17	Main & Sub Distribution Boards (MCB + RCCB Protection) Schneider / ABB · 8-way / 12-way vertical TPN DB with 30mA earth leakage protection (Each Floor Electrical Shaft)	2 Units	18,000	**36,000**

2. PLUMBING SYSTEMS & STORAGE — Subtotal: 50,000

SL	ITEM / SPECIFICATION	QTY / UNIT	RATE ()	AMOUNT
18	Overhead Domestic Water Storage Tank (1500 Litres) Sintex / Supreme · 4-layer anti-bacterial UV-stabilized rotational molded tank (Terrace Overhead Slab)	1 Units	18,000	**18,000**
19	Automatic Booster Pressure Pump & Sump Submersible Pump Grundfos / Wilo · 0.75 HP automatic pressure booster pump with dry run protection (Sump & Terrace Delivery Line)	1 Units	32,000	**32,000**

3. SANITARYWARE & BATHROOM FIXTURES — Subtotal: 1,57,000

SL	ITEM / SPECIFICATION	QTY / UNIT	RATE ()	AMOUNT
10	Wall-Hung EWC with Soft-Close Seat & Concealed Flush Valve Premium (Jaquar / Kohler / Grohe) · Rimless ceramic bowl, dual-flush water saving cistern (Bathrooms & Powder Rooms)	4 Sets	15,200	**60,800**
11	Countertop / Wall-Hung Wash Basin with Single-Lever Pillar Cock Premium (Jaquar / Kohler / Grohe) · Vitreous china basin with brass chrome-plated tap (Bathrooms & Dining Vanity)	4 Sets	9,500	**38,000**
12	Concealed Bath Diverter & Overhead Rain Shower Set Premium (Jaquar / Kohler / Grohe) · Thermostatic cartridge with 200mm SS rain shower head (Bathrooms)	3 Sets	9,500	**28,500**
13	Health Faucet Hand Spray with 1.2m SS Braided Hose & Hook Premium (Jaquar / Kohler / Grohe) · ABS body with SS braided anti-burst pressure hose (All WCs)	4 Sets	3,800	**15,200**
14	Stainless Steel Double-Bowl Kitchen Sink with Drainboard Nirali / Franke · AISI 304 Grade (1.2mm thickness) with swivel neck mixer tap (Kitchen Area)	1 Sets	14,500	**14,500**

4. DOORS, WINDOWS & GLAZING — Subtotal: ₹1,41,950

SL	ITEM / SPECIFICATION	QTY / UNIT	RATE (₹)	AMOUNT
1	Main Entrance Grand Door (Frame + Shutter + Hardware + Lock) Premium Teak · 4.0 ft × 7.0 ft (Solid Teak Wood) (Main Entrance)	1 Sets	₹65,000	**₹65,000**
2	Internal Bedroom & Living Space Door Set (Hardwood Frame + Shutter + Mortise) Flush Door · 3.0 ft × 7.0 ft (Hardwood Frame + BWP Shutter) (Bedrooms & Enclosed Rooms)	7 Sets	₹12,500	**₹87,500**
3	Waterproof Bathroom Door Set (WPC/FRP Frame + Water-Resistant Shutter) FRP / WPC Laminated · 2.5 ft × 7.0 ft (Waterproof WPC / FRP Composite) (Bathrooms & Powder Rooms)	4 Sets	₹13,500	**₹54,000**
4	Bedroom 2-Track Glazed Window with Mosquito Mesh (3 Nos) uPVC · 5.0 ft × 4.0 ft (3 × 20 sq.ft = 60 sq.ft) – uPVC – Standard uPVC (Bedrooms)	60 sq.ft	₹550	**₹33,000**
5	Living Room 3-Track Picture Window (Full Height) (2 Nos) uPVC · 6.0 ft × 5.0 ft (2 × 30 sq.ft = 60 sq.ft) – uPVC – Standard uPVC (Living Room)	60 sq.ft	₹550	**₹33,000**
6	Kitchen Sliding Window with Exhaust Louver Provision (1 Nos) uPVC · 4.0 ft × 3.0 ft (1 × 12 sq.ft = 12 sq.ft) – uPVC – Standard uPVC (Kitchen)	12 sq.ft	₹550	**₹6,600**
7	Bathroom Louvered Ventilator with Exhaust Opening (4 Nos) uPVC · 2.0 ft × 3.0 ft (4 × 6 sq.ft = 24 sq.ft) – uPVC – Standard uPVC (Bathrooms / Toilets)	24 sq.ft	₹550	**₹13,200**
8	Dining Room Glazed Sliding Window (1 Nos) uPVC · 5.0 ft × 3.0 ft (1 × 15 sq.ft = 15 sq.ft) – uPVC – Standard uPVC (Dining Area)	15 sq.ft	₹550	**₹8,250**
9	Utility Service Ventilator Window (1 Nos) uPVC · 4.0 ft × 2.0 ft (1 × 8 sq.ft = 8 sq.ft) – uPVC – Standard uPVC (Utility Area)	8 sq.ft	₹550	**₹4,400**
25	Balcony French Sliding Door Set (2.5-Track Aluminium / UPVC) Fenesta / Geeta Aluminium · 5.0 ft × 7.0 ft 2.5-track sliding door with 6mm toughened glass and SS mosquito mesh (Balconies & Open Sit-outs)	2 Sets	₹18,500	**₹37,000**

SECTION C TOTAL — WHAT WE INSTALL (FIXTURES & SERVICES) ₹7,55,590

SERVICES & MEP ENGINEERING DISCLAIMER

Electrical point distribution, wire gauges, plumbing CPVC/SWR pipe sizing, and sanitary fixture allocations are derived from architectural space rules and benchmark engineering standards. Final conductor sizing, circuit breaker protection, water pressure calculations, and sewer invert levels must be validated by appointed MEP consultants before site rough-in.

SECTION D — WHAT IT COSTS · COST SUMMARY & COMMERCIAL DETAILS

TRADE CATEGORY	AMOUNT (INR)	% OF TOTAL
Physical Materials (What We Consume)	22,57,097	40.6%
Fixtures & Equipment (What We Install)	7,55,590	13.6%
Labour (Civil & Finishing Trades)	8,23,168	14.8%
Contractor Execution Margin (15%)	5,75,378	10.4%
Contingency Reserve	2,30,151	4.1%
Professional Architecture & Engineering Fees	1,91,793	3.5%
Contractor GST & Statutory Taxes	7,24,977	13%
TOTAL ESTIMATED PROJECT COST (ALL-INCLUSIVE)	**55,58,154**	**100.0%**

BASE CONSTRUCTION	CONTRACTOR MARGIN	CONTINGENCY	PROFESSIONAL FEES	GST / TAXES
38,35,855	5,75,378	2,30,151	1,91,793	7,24,977

PAYMENT PLAN — MILESTONE DISBURSEMENT SCHEDULE

STAGE / CONSTRUCTION MILESTONE	DISBURSEMENT	STAGE %
Stage 1: Booking & Agreement Initial commitment, site survey, design approval and agreement signing.	2,77,908	5%
Stage 2: Foundation Completion All footing pits dug, PCC bed poured, column footings and pedestals cast.	6,66,978	12%
Stage 3: Plinth Level Plinth beams cast, earth backfilled and compacted, DPC layer complete.	5,55,815	10%
Stage 4: Ground Floor Slab Ground floor columns cast, roof slab shuttering and M25 RMC pour complete.	8,33,723	15%
Stage 5: First Floor Structure First floor columns, beams and slab completed with 21-day curing.	6,66,978	12%
Stage 6: Roof Slab Completion Top floor slab cast and cured. Full structural frame standing.	5,55,815	10%
Stage 7: Brick & Plaster Done All masonry walls erected, chicken mesh applied, double coat plaster complete.	5,55,815	10%
Stage 8: MEP Roughing Done Concealed electrical conduit, plumbing pipe layout and hydro testing complete.	4,44,652	8%
Stage 9: Flooring & Painting Vitrified tiles laid, granite steps installed, painting primer + finish coats.	4,44,652	8%
Stage 10: Fixtures & Finishes CP fittings, sanitary ware, modular switches, lights, doors and windows fixed.	3,89,071	7%
Stage 11: Final Handover Deep cleaning, snag list clearance, OC certificate and key handover.	1,66,747	3%
TOTAL — ALL MILESTONES	**55,58,154**	**100.0%**

IMPORTANT ESTIMATE NOTE

This is an early estimate to help you plan. Final costs and quantities may change after the site, drawings and material choices are checked.

RATE MASTER SOURCE & ENGINE METADATA

Dataset: HUTTY-RM-2026.1 · Provider: Hutty Baseline Rate Dataset · Engine: v2.6.0 · Mode: 2026-Q1 Fallback / Baseline Rates · Basis: Bangalore Market Q1 2026

IMPORTANT — PRELIMINARY ESTIMATE & ENGINEERING NOTICE

· Generated using Hutty's preliminary quantity surveying estimation rules. Final structural, geotechnical, and MEP engineering drawings must be certified by appointed consultants.
· Actual quantities and costs may vary based on architectural drawings, soil strata, construction methods, brand specifications, supplier quotations, and prevailing market rates.

SECTION E • CONTRACTOR QUOTE AUDIT & SENSITIVITY (PREMIUM DELIVERABLE)

Independent QS vetting benchmarks, finish sensitivity variance, and multi-scenario footprint comparison.

1. KEY TRADE MARKET TOLERANCES (BANGALORE Q1 2026)

MATERIAL / TRADE DESCRIPTION	UNIT	MARKET BENCHMARK	ALLOWABLE VARIANCE
Structural TMT Steel (Fe 550D)	Per Kg	**68 – 76**	±5% tolerance
53-Grade Portland Cement	50kg Bag	**380 – 420**	±4% tolerance
Solid Concrete Masonry Blocks (6")	Per Block	**42 – 48**	±5% tolerance
Civil RCC Labour (Framed Structure)	Per sq.ft BUA	**240 – 280**	±6% tolerance
Tile Laying & Grouting Labour	Per sq.ft	**35 – 45**	±8% tolerance
Interior Emulsion Painting (2 Coats + Putty)	Per sq.ft	**18 – 26**	±7% tolerance

2. HIGH-RISK MISSING SCOPE CHECKLIST (CONTRACTOR REDLINES)

[!] **Soil Bearing Capacity Test:** Frequently omitted by turnkey contractors; demand written geotechnical soil report before footing depth sign-off.

[!] **Temporary 3-Phase Power & Water:** Verify whether temporary power meter deposit, wiring, and borewell water for curing are included in contractor's quote.

[!] **Compound Wall & Gate Columns:** Often charged as an extra variation cost. Ensure linear footage and foundation depth are explicitly documented.

[!] **Sump Waterproofing & Debris Disposal:** Verify crystalline chemical waterproofing on underground tanks and periodic carting of construction debris away from site.

3. FINISH SPECIFICATION SENSITIVITY MATRIX (1,440 SQ.FT BUA)

SPECIFICATION PACKAGE	MATERIAL STANDARDS & FITTINGS	EST. RATE/SQFT	PROJECT VARIANCE
Standard Specification	Vitrified 2x2, standard UPVC, OBD paint, baseline CP	₹1,950	- ₹27,50,400
Premium (Current Baseline)	GVT 4x2, Schuco UPVC, Royal luxury emulsion, Jaguar fittings	**₹3,860**	**Baseline**
Luxury Specification	Italian marble, thermal-break aluminium, Grohe/Kohler, smart automation	₹2,850	+ ₹0

4. MULTI-SCENARIO LAYOUT COMPARISON ON PLOT (40' × 30')

LAYOUT SCENARIO	BUILT-UP AREA (BUA)	ESTIMATED BUDGET	EFFECTIVE RATE
Scenario A: Single Floor (Compact)	720 sq.ft	₹27,79,200	₹3,860/sqft
Scenario B: Current Plan (G+1)	**1,440 sq.ft**	**₹55,58,154**	**₹3,860/sqft**
Scenario C: +1 Floor (Rental Unit)	2,160 sq.ft	₹80,03,850	₹3,706/sqft

IMPORTANT ESTIMATE NOTE

This is an early estimate to help you plan. Final costs and quantities may change after the site, drawings and material choices are checked.